



Single Combination Building Inspection Process

"Small Solar Photovoltaic Electrical Systems"



California Building Officials Training Institute proudly presents:

Small Solar Photovoltaic Systems

"Single-Combination Inspection Process"

Are you an AHJ interested in proven effective methods for a "singleinspection process of small PV systems" eligible for State mandated expedited permitting?

Are you an AHJ interested in a point by point interpretation and opinion regarding the 19 point checklist from the California Solar Permitting Guidebook?

Are you a PV installer and want transparency and understanding of the single-inspection process?

If you answered yes to any of the above, this presentation will be beneficial for you and or your entire staff. This presentation will help all parties understand a sound:

"Single-Combination Inspection Process" to avoid "Re-inspections."

This training will address related California Electrical Code Article 690 and 705 requirements as well as the 19 point inspection checklist of the Solar Permitting Guidebook. It will benefit building officials, plan check staff, and inspection staff as it will highlight "bigger picture code requirements and intent" and sound "<u>single inspection methodologies</u>" proven to be practical for compliance with new law. The training will also benefit solar energy system contractors, installers, manufactures and project design entities as failed inspections create more work for both AHJ's and all other solar community stake holders.

Instructor: Sparky Cohen, CBO

Sparky Cohen is a fourth generation finish carpenter from a family of woodworkers and California B Licensed Contractors.

Sparky started working for a building department in 1989 as a Combination Building Inspector. He is currently the Building Official for the Building and Safety Division and he is the Chief Code Enforcement Officer for the Code Enforcement Section of the City of Calabasas.

Sparky has secured the following certifications:

Building Official Building Plans Examiner Electrical Plans Examiner Electrical Inspector Septic System Inspector Plumbing Inspector

A word about training ...

The views and opinions expressed in this presentation by the instructors are based upon their own experiences and understanding of the topic. They do not necessarily reflect the position of CALBO, local ICC Chapters, US DOE, CESA, or SEAC. Examples based on experiences are only examples.

Instructor: Don Hughes

Don Hughes is the Codes and Standards Specialist for the Center for Sustainable Energy, he is a leading expert regarding solar photovoltaic system permitting, inspecting and codes and standards. With over 30 years combined experience as an Electrician, Electrical Inspector and Chief Electrical Inspector he has served as the President, Vice President and Treasurer for the IAEI Northern California Chapter and has provided AHJ perspective to the United States Department of Energy, The California State Governor's Office of Planning and Research, The Interstate Renewable Energy Council, and Underwriter's Laboratories. He currently serves on all U.L. Standards Technical Panels for Solar PV, and is an IAEI/ IASET Trained Solar PV instructor.



Presentation Index

	End Note	Slide
	Pg. No.	Number
Presentation Title - Description	89*	1
Vauxinatyuatawla		2
		Ζ
What is considered a small PV system		3
Genesis of subject - Historic legislation		4
AB2188 - "one-building inspection limitation"		5
L. A. Pasin and Ventura ICC Joint Inspection Committee Pullatin Program		
Based upon a survey of combination building inspectors	89-92*	6
Bused upon a survey of combination building inspectors		
Joint Inspection Committee Bulletin's 1-5	93-98*	7
Joint Inspection Committee Bulletin's 6-10	99-111*	8
		0 10
Photos of typical small PV system		9 - 10
How a typical small PV system works		11
Presentation does not address thermal systems		12
California law	112*	13
The factor decision of the Although the second of the second		
I ypical codes used by AHJ - Building code library		14
Current California Building Codes		15
		15
First Uniform Building Code - Goals and administrative processes	112*	16
1927 Uniform Building Code - Required inspections		17
Dequired inspections Deef underlayment 2		10
Required inspections - Roof underlayment ?		18
Required inspections -Roof flashing?		19
Required inspections - Frame		20
Required inspections - Inspector's, do not encourage in process inspections		21
Cool of Colifornia Color Dorreittica Cuidabaal	442*	22
Goal of California Solar Permitting Guidebook	11Z"	
Customer service		23-24
	1	:

	End Note	Slide
	Pg. No.	Number
Customer service - AB2188 law intent		25
Dhata waa haa tillaad aa too aattaa atta		24.27
Photographs utilized as inspection aid		26-27
Accors to work Invasivo or dostructivo		20
		20
CAL/OSHA - Access to work - Is it safe?	114-178*	29
	114 120	27
With safe access to roof - Can roof materials still be damaged?		30
		50
Smoke detector and carbon monoxide alarm affidavits		31
Correction notice righting basics		32
Correction notice righting basics - Methods of construction		33
Correction notice righting basics - Inaccurate construction Plans		34
Correction notice righting basics - Unlawful structure		35
Is existing construction lawful - Estopple		36
Primary goal of all building codes		37
Primary goal of fire codes		38
Primary goal of electrical code		39
Primary goal of residential code		40
Primary goal of plumbing code		41
Primary goal of mechanical code		42
Building inspection is not quality control		43
Robotic enforcement of building codes		44
Use of inspection checklists	159-165*	45-46
Other helpful checklists and documents	128-155*	47
		10 75
PV Systems - Threat to firefighters	156 +165*	48-52
		F0 F1
Hazards and electricity	156*	53-56

	End Note	Slide
Electrical equipment is installed in a neat and workmanlike manner	1 g. 110.	57
Electrical equipment is installed in a neat and workmanlike manner - Photos		58-68
The future - Technology - Legislation		69
End first part of session		70
		70
Second part of session - the single inspection - 19 point checklist		
Don Hughes courtesy of CSE and SunShot		71
AB2188		72-75
Attitude - Communication - Preparation		76-78
Installers properly trained - access to and knowledge of equipment		79
New laws and technology - AHJ's need to be more efficient		80-82
Corrective measures performed during inspection		83
New product safety standards		84
AHJ checklists and processes readily available to contractors		85
California Solar Permitting Guidebook - Tool kit 7 Section 1 and 2	158*	86-87
The 19 point inspection checklist:	159-165*	
Equipment off		88
No. 1 All work in a neat and workmanlike manner		89-92
No. 2 PV module model number, quantity and location		93-95
No. 3 Array mounting and structural connections		96-99
No. 4 Roof penetrations flashed/sealed		100-103
No. 5 Array cables protected from physical damage		104-105
No. 6 Conduit installed to CPC P221.2 and CEC 600.4(E)		104
		100

		End Note	Slide
		Pg. No.	Number
No. 7	Firefighter access	165*	107-109
No. 8	Required fire classification		110
No. 9	Grounding/bonding of rack and modules		111-114
No. 10	Equipment listing		115
No. 11	Inverter listing marked "interactive"		116
No. 12	Ungrounded inverter conductors - CEC 690 35		117-120
1101 12			117 120
No. 13	Conductors cable and conduit types sizes and markings	15/*	121-122
110.15	conductors, cable and conduit types, sizes and markings	134	
No. 14	Main broaker and everywrent protection	15/*	122 124
NO. 14	Main breaker and overcurrent protection	104"	123-124
11.45			405 407
No. 15	Disconnecting means	154*	125-127
No. 16	Output circuit breaker opposite end of bus of utility supply		128
No. 17	Labels and signs	155*	129-130
No. 18	PV system connection to grounding electrode conductor	154*	131
No. 19	Access and working space to PV equipment		132
	51 11		
End part ty	wo of session		133
Regin part	three of session - SEAC Single Inspection Recommendations		
Degin pare	three of session - SEAC single inspection recommendations		
Who is SEA	Cand what is their objective Issue Statement 1		12/ 1/1
WIIO IS SLA			134-141
Laura Chata			
Issue State	ment 1 - Recommendations 1-6:		
			4.42
No. 1	Installer qualifications		142
No. 2	Roof access and CAL/OSHA		143
No. 3	Approved constructions plans available		144
No. 4	Affidavits		145
No. 5	On-going training for inspectors and contractors		146
No 6	AHJ and photographic assistance for inspections		147
1.0.0			
		1	

Pg. No. Number Issue Statement 1 - Photographic documentation 148-149 SEAC Photo guideline recommendations 1-9:		End Note	Slide
Issue Statement 1 - Photographic documentation 148-149 SEAC Photo guideline recommendations 1-9:		Pg. No.	Number
SEAC Photo guideline recommendations 1-9:	Issue Statement 1 - Photographic documentation		148-149
No. 1 PV module label 150 No. 2 Method of flashings and attachments 151 No. 3 Grounding and bonding of modules and racking 152 No. 4 Wire management under modules 153 No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155	SEAC Photo guideline recommendations 1-9:		
No. 1 PV module label 150 No. 2 Method of flashings and attachments 151 No. 3 Grounding and bonding of modules and racking 152 No. 4 Wire management under modules 153 No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155	SLAC FILOLO guideline recommendations 1-7.		
No. 2 Method of flashings and attachments 151 No. 3 Grounding and bonding of modules and racking 152 No. 4 Wire management under modules 153 No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155	No. 1 PV module label		150
No. 2 Method of flashings and attachments 151 No. 3 Grounding and bonding of modules and racking 152 No. 4 Wire management under modules 153 No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155			
No. 3 Grounding and bonding of modules and racking 152 No. 4 Wire management under modules 153 No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155	No. 2 Method of flashings and attachments		151
No. 3 Grounding and bonding of modules and racking 152 No. 4 Wire management under modules 153 No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155			
No. 4 Wire management under modules 153 No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155	No. 3 Grounding and bonding of modules and racking		152
No. 4 Wire management under modules 153 No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155			
No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155	No. 4 Wire management under modules		153
No. 5 Conduit penetrations of roof and inaccessible areas 154 No. 6 Height of conduit above roof - de-rate calculations 155	No. E. Conduit non-structions of reaf and increasible areas		454
No. 6 Height of conduit above roof - de-rate calculations 155	No. 5 Conduit penetrations of roof and inaccessible areas		154
	No. 6. Height of conduit above roof - de-rate calculations		155
			IJ
NO / CONDUIT IN ATTIC	No. 7. Conduit in attic		156
			150
No. 8 Junction and combiner boxes 157	No. 8 Junction and combiner boxes		157
No. 9 Labels not readily accessible 158	No. 9 Labels not readily accessible		158
Issue Statement 1 applicable to whom 159	Issue Statement 1 applicable to whom		159
			140
End of presentation 160	End of presentation		160
End Notost 90 165*	End Notos*	90 145*	
Elid Notes" 69-100"		09-100"	

Power Point



































CALBO TRAINING INSTITUTE		
Customer Service		
Courteous – have a smile in your voice – are you approachable?		
Supportive – can do attitude – understand the customers goals and make them a reality.		
Receptive and responsive – time is money – give inspection times; promptly return phone calls and emails.		
Be flexible – facilitate practicable decisions when code intent is achieved.		









CALBO TRAINING INSTITUTE Smoke Detector and Carbon Monoxide Alarm Affidavits Are Highly Encouraged		
<text><text><text><text><text></text></text></text></text></text>	<text><text><text></text></text></text>	
Norma Calo Resultive II, 2021 August 473	Notes da Novelle 3, 50 April 73	Rector Sec. Nameller 43, 503 Aug. 1-473
Kapadan Carrinas		

Calbo TRAINING INSTITUTE Correction Notice Writing Basics	
Clearly describe "observations."	
Clearly describe corrective actions necessary.	
Cite accurate applicable Code Section.	
If your signature is not plainly legible - legibly print your name.	
	32













CALBO TRAINING INSTITUTE		
Building Inspection is not	"Quality Control"	
Quality Control	Customer Service	
Quality control is a Civil matter between Contractor		
Project Design Team, and Homeowner.		
When quality control is desired by permittee,		
construction management experts are often utilized.		
	43	





The installers responsibility to have the approved standard plans at the project site. - OR -The installer and the inspectors familiarity with fundamental requirements detailed in the California Electrical Code Chapters 1 through 4.



Installation Of A Small PV System



Fire Fighters Are At Risk Due To The Presence Of The System

48*




























72



74































CALBO TRAINING INSTITUTE

5. Array exposed cables are properly secured, supported and routed to prevent physical damage





POORLY ROUTED AND UNSECURED – "LAYING ON ROOF SURFACE AND VENT"

104







Page | 63





Page | 64
























130













CALBO TRAINING INSTITUTE AB2188 Section 65850.5 of the Government Code is amended to read: 65850.5. (h) For a small residential rooftop solar energy system eligible for expedited review, only one inspection shall be required, which shall be done in a timely manner and may include a consolidated inspection, except that a separate fire safety inspection may be performed in a city, county, or city and county that does not have an agreement with a local fire authority to conduct a fire safety inspection on behalf of the fire authority. If a small residential rooftop solar energy system fails inspection, a subsequent inspection is authorized, however the subsequent inspection need not conform to the requirements of this subdivision. 139

CALBO TRAINING INSTITUTE

Current Status

 SEAC has identified successful single inspection procedures currently in use by several jurisdictions. In addition, SEAC is providing innovative recommendations that can be used to develop AB 2188 compliant single inspection procedures.

140

CALBO TRAINING INSTITUTE Key considerations The objective of this briefing is to facilitate system approval in one inspection. Many of the solutions simply require a greater education, relationship, and communication of expectations between the AHJ and the installer. 141 CALBO TRAINING INSTITUTE Recommendations 1) The installer should ensure that a qualified individual who is familiar with the applicable codes and installation procedures be onsite at time of inspection to provide access to the system and all components and to answer any questions from the inspector. 142





















Power Point Endnotes

(Slide 2) This presentation and the implementation of AB2188 in Ventura County and Los Angeles County would not be a success without the generous support of Don Hughes, Bill Brooks, Mustafa Kashe, John Wiles, Stuart Tom, Pete Jackson, Steven Jones, Pat Healy, Jason Reithoffer, Dan Chavin, and Steve Berry.

(Slide 6) ICC Ventura Region Chapter and ICC Los Angeles Basin Chapter Joint Inspection Committee Single Combination Inspection Process - "Small PV Bulletin Program."







Preface

Solar photovoltaic electrical technology and legislative laws are transcending current building codes. In January of 2015 in response to California Assembly Bill 2188, the Board of Directors of the Los Angeles Basin Chapter and the Ventura Region Chapter of ICC directed their respective Inspection Committees ("Joint Inspection Committee") to analyze the inspection challenges known to be looming. In response to the direction the Committee created the "Small Solar System One-Inspection Process Bulletin Program." The program is a series of documents related to proven successful practices and useful information regarding the single inspection process of small solar photovoltaic electrical systems.

The Joint Inspection Committee recommends that the Board of Directors recognize the program and make the document/s available on the Chapters websites. Building Departments within the Los Angeles Basin and Ventura Region should also be encouraged to support the program and post the documents on their websites as well.

Acknowledgements

Each and every joint inspection committee member should be commended for their review of the draft and final documents. In addition, the tremendous efforts and contributions of the Solar Energy Action Committee (SEAC), which was formulated by the County of Los Angeles Department of Public Works Building and Safety Division, should be commended. The Chairman of the Joint Inspection Committee is an active member of SEAC and this bulletin program gleans much of their positive work. To date, four "issue statements" created by SEAC are supported by the Joint Inspection Committee and are part of this bulletin program. The Joint Inspection Committee also shares SEAC's message which is as follows:

"The State of California has an aggressive solar energy growth plan. With these goals in mind, a diverse group of professionals has been gathered to form the Solar Energy Action Committee ("SEAC"). SEACs mission is to assist the solar industry by outlining available solutions to provide a transparent roadmap for achieving a code compliant and efficient solar installation."

June 15, 2016

Introduction





Acknowledgements Continued

Joint Inspection Committee:

Sparky Cohen Steve Berry Steve Stoltze Matt Wyatt Sandi McCracken Michael Pauly

> Dan Freleaux Jesse DeAnda Tim Griffith Ayla Jefferson Scott Klepetar

Building Official – Committee Chairman Supervising Building Inspector **Building Inspection Supervisor** Supervising Building Inspector Senior Manager-Metal Building and Fabrication Accreditation Programs Lead Combination Building Inspector Miguel Garcia Supervising Building and Safety Engineering Specialist District Building and Safety Engineering Associate E-Government Manager Senior Building Inspector **Building Official Branch Operations Manager**

City of Calabasas City of Simi Valley City of Thousand Oaks County of Ventura International Accreditation Service

City of Santa Monica County of Los Angeles County of Los Angeles City of Beverly Hills City of Los Angeles City of Alhambra /Transtech Engineers North Hollywood Sunrun Inc.

SEAC:

Don Hughes Hector Bordas Paula Melon Alan Fields Andrew Henning Behzad Eghtesady Craig Carni Gilbert Aceves Jason Rondou Jeff Spies lim Cahill John Taecker Kevin Reinertson Mark Baldassari Mostafa Kashe Patrick Healy Pete Jackson Robert Vinje Roy Allen Shai Bergerfroind Steve Jones Stuart Tom Sunny Rai Tiffany Maycumber

Retired Electrical Inspector - Santa Clara County Assistant Deputy Director – Building and Safety Project Administrator AHJ & Utility Specialist Deputy State Fire Marshal III (Specialist) Chief Electrical Inspector Chief Technology Officer and Founder Technical Specialist Scientist Solar Programs Manager Sr. Director of Policy Regional Vice President Sr. Regulatory Engineer Deputy Fire Marshal Director, Codes and Standards Chief Electrical Inspector Chief FPM Inspector Chief Electrical Inspector Vice Pres of Utility and Commercial EPC Ron Mulick Chairman of CALSEIA LA Chapter - Pres/CEO of Solartronics Technical Sales Support Engineer Director of Operations Velocity, Operations Assistant Building Official Fire Marshal Vice President, Global Business Line Leader Technical Advisor

Center For Sustainable Energy County of Los Angeles Optibiz Sungevity CalFire - Office of the State Fire Marshal City of Los Angeles IronRidge SCE City of Los Angeles DWP CalSEIA / QuickMount PV SolarCity Underwriters Laboratory **Riverside County Fire Department** Enphase County of Los Angeles County of San Diego City of Bakersfield SunPower Corporation Solartronics ABB Inc. Verengo Solar City of Oceanside City of Glendale Fire Department Intertek, ETL San Diego Gas & Electric

June 15, 2016

Introduction

Page 2 of 3



ICC Los Angeles Basin Chapter and Ventura Region Chapter Joint Inspection Committee "Small Solar System One-Inspection Process Bulletin Program"



Program Overview

The "Small Solar System - One Inspection Process - Bulletin Program" is a series of bulletins that describe proven recommended practices and useful information¹ in response to "Assembly Bill 2188" - California Government Code Section 65850.5 (h). The program is limited to expedited permitting for small solar photovoltaic "PV" electrical energy systems. The program is intended to benefit any stakeholder of the electrical solar photovoltaic industry.

What is considered a small solar photovoltaic electrical energy system (small PV system)? It's a system with an alternate current nameplate rating of 10 kilowatts or less and the solar panels are on the roof of a single or duplex family home. The passage of Government Code Section 65850.5 (h) which is the genesis of this program is as follows:

"For a small residential rooftop solar energy system eligible for expedited review, only one inspection shall be required, which shall be done in a timely manner and may include a consolidated inspection, except that a separate fire safety inspection may be performed in a city, county, or city and county that does not have an agreement with a local fire authority to conduct a fire safety inspection on behalf of the fire authority. If a small residential rooftop solar energy system fails inspection, a subsequent inspection is authorized, however the subsequent inspection need not conform to the requirements of this subdivision."

For the "Single Combination Inspection" of a small PV system, if the inspector has a recognized standard plan, the California Solar Guidebook tool Kit No. 7 (19 point inspection checklist and comprehensive inspection reference), and most importantly, an understanding of the intent of the new law and the primary California Building Codes, the Joint Inspection Committee believes that to be the best strategy for the successful and efficient performance of the single inspection. These bulletins can be used in a variety of ways to build an inspectors confidence level related to the aforementioned. These bulletins can also stand alone as separate useful informational documents; however, the advantages of the program as a whole are most useful after attending a related training session.

June 15, 2016

Introduction

Page 3 of 3

¹ New bulletins may be added and existing bulletins may be updated from time to time. New or revised bulletins will be reflected with the word "revised" and new date in the footer of the impacted bulletin.





Bulletin 1 - Intent of requirement for work to be installed in a workman like manner.

"Good or poor workmanship should set the tone of the inspection."

"Good workmanship should result in an inspection that is shorter in time than that of an inspection with poor workmanship."

Good workmanship, good access, and good photographs, should result in an inspection with a very short duration of time." (See Bulleting 2 regarding the effective use of photographs.)

Building inspectors are not agents for quality control, nor do they enforce requirements of the California State Constructors License Board. However, a project with an obvious lack of workmanship will frequently lead to close scrutiny/attention to detail of the project from the building inspector. A building inspector should avoid citing California Electrical Code Article 110.12 and the lack of workmanship or Article 690-3 (E)¹ as a "code violation." The specific sub article of the code pertaining to the specific non-compliant part of the proposed installation should be cited. In example, should a contractor utilize a length of Electrical Metallic Tubing that has not been bent with approved bending equipment, the inspector should cite Article 358.24 which states:

"Bends – how made. Bends shall be made so that the tubing is not damaged and the internal diameter of the tubing is not effectively reduced. The radius of the curve of any field bend to the centerline of the tubing shall not be less than shown in Table 2, Chapter 9 for oneshot and full shoe benders."

Poor workmanship

Poor workmanship





Workmanlike manner



¹ Article 1100 and the definition of qualified person also has a Informational Note that references NFPA 70E-2009. The reference document is an OSHA recognized electrical worker safety document that general involves higher voltage/high ampacity 3 phase systems. It would not be appropriate to apply the training to small PV systems.

June 15, 2016

Bulletin 1





Bulletin 2 – How and when to utilize photographs – work concealed without observations or otherwise difficult to view.

A very good alternative to confirm criteria within difficult to access areas or areas that are obscured for close viewing, is to utilize photographs. Photographs should be used as an inspection aid – they should not be used to substitute for an on-site inspection.

Many proactive contractors are photo documenting all aspects of their installations for their own quality control and protection against customer claims at a later date. These photographs, and or on the spot photographs requested to be taken by the building inspector, can prove a valuable time saver for both the building inspector and the contractor.

The law is clear - only one-single inspection shall be provided. An AHJ should not encourage the contractor to provide a "rough inspection" under any circumstance. A building inspector should not conveniently "drop in" on a project site while the contractor is in the process of installing a small PV system. The aforementioned introduces a potential allegation of misfeasance or malfeasance and allegations are tremendously uncomfortable.

Malfeasance - the performance of an act that is legally unjustified, harmful, or contrary to law Misfeasance - the wrongful performance of a normally lawful act Nonfeasance - the omission of some act that ought to have been performed

Invasive or destructive methods requested by the inspector (such as removing PV panels or roofing tiles) are a disservice. Moreover, the California Building Codes do not mandate a building inspector confirm the installations to the extent of such detail. In example, requesting roofing tile and or a PV panel to be removed to confirm quality control of a roof penetration is not required by either by the California Electrical Code or the California Residential Code. More specifically:

"CRC Section 905.3.3 –Underlayment Inspection Is Not Required."

"CRC Section 905.3.8 -Roof Flashing Inspection Is Not Required."

Again, a very good alternative to confirm criteria within difficult to access areas, or areas that are obscured for close viewing, or areas concealed by construction is to utilize photographs. See Bulletin 7 section 6 for reasonable photo guidelines and Bulletin 4 regarding access to roofs.



June 15, 2016

Bulletin 2





Bulletin 3 - Installations on existing construction without benefit of building permits.

Is the existing structure lawful? Did the building inspector just inadvertently approve a room addition?

This bulletin assumes that in most cases the permit for the small PV system was issued on-line and did not have the benefit of a historic permit review process from a permit technician or a plans examiner. The building inspector in these cases, is the last and only line of defense as keeper of accurate permanent records. Reviewing existing permit records before the inspection is valuable - inadvertently approving existing work leads to substantial aggravation for AHJ's down the road.

A term that should be considered is an "Estopple - Detrimental Reliance on a Document or Action."

What is Estopple?

The complaining party is asking the AHJ to "Stop" an action.

What is Detrimental Reliance on a Document or Action?

Reliance on Document -

The recipient of an AHJ enforcement action is claiming that since they relied on the building department record/s as being accurate, it was assumed everything was legal and they purchased the property.

Reliance on actions -

An AHJ's permit/s allowed them to construct a project of a certain size or in a certain location. An AHJ representative at a later point in time states the square feet size of the structure is excessive and or is in a location that is not permissive. The property owner may use "reliance on actions" as their defensive allegation.

These arguments get dramatically stronger each time the property is sold.

Hypothetically assume the following:

The AHJ building permit records reflect that a single family dwelling is 1200 square feet in size with a 250 square feet detached garage are constructed in the year 1970. There are directly related Plumbing, Mechanical and Electrical permits issued in 1970 as well. Between the year 1970 and 2016 there are no other building permits issued that justify other physical improvements to the dwelling.

In 2016, a small PV permit is issued on-line and the application states the dwelling is 2500 square feet in size, with 500 square feet in size attached garage. There is also a 200 square feet solid roofed attached carport on the side yard depicted. The site plan proposes that PV panels are to be installed on both the attached garage roof and a portion of the dwelling that has been expanded. Conduit from the PV system is also fastened to the top of the carport.

June 15, 2016

Bulletin 3



ICC Los Angeles Basin Chapter and Ventura Region Chapter Joint Inspection Committee "Small Solar System One-Inspection Process Bulletin Program"



The building inspector provides inspection approval of the small PV system, no corrective measures are requested during the single final inspection. Did the inspector just inadvertently approve the expansion of the dwelling? The attached garage? How about the carport?

Example 1 - compounded. The building inspector has not reviewed the existing permit records and does not notice that the home is significantly different than the original building permits. The inspector has entered the attached garage and is trying to verify an existing water bond connection on a water heater installed in that garage. The inspector does not see a water bond connection and the contractor does not know the location of an existing connection – if there is one somewhere else. The contractor inquires if it would be acceptable to simply install a new solid number 8 copper conductor from the service panel to the cold water piping at the water heater. The inspector agrees and leaves a correction notice to "install a water bond at the cold water piping of the water heater or verify the connection of an existing water bond at a different location." No other written or verbal direction is cited by the inspector, the contractor installs the new water bond to the water heater and the project receives a final inspection.

Example 1 – potential issue: At some point in time in the future, the home is sold. The property is subject of code enforcement actions and the AHJ demands the property owner secure building permits for the new attached garage. The new owner claims they relied on the building department records to be accurate and assumed the garage was lawful. The Estopple – detrimental reliance on actions and documents are both compelling and problematic for the AHJ. (The argument is substantially more problematic if the new homeowner has a copy of the correction notice that only addresses the water bond to the water heater in the garage and does not address the structure itself.)

Example 2 – The carport extends to within one foot of the side yard property line. The inspector is certain that the carport is not benefit of building permits and inspection approvals and leaves corrective measure direction in writing to either secure permits and or remove the carport. The Contractor and property owner choose to demolish the carport and in turn the PV system permit receives a final inspection one week later. At some point in time in the future, the home is sold. The property is subject of code enforcement actions and the AHJ demands the property owner secure building permits for the homes expansion and the attached garage. The Estopple – detrimental reliance on actions and documents are both compelling and problematic for the AHJ as it is claimed the AHJ did a code compliance inspection for the property during the first and final re-inspection of the PV system via the order to demolish the carport.

Affidavits or AHJ waiver statements/clause notes made part of an issued PV permit may be helpful during other code enforcement actions if the same person owns the property [emphasis added – may – the scenarios above can still cause aggravation for the AHJ]. However, Affidavits or AHJ waiver statements/clause notes made part of an issued PV permit do not lessen the arguments as stated above once a property is sold.

An inspectors review of the existing permit records is the first and foremost best line of defense for the AHJ. Moreover, if an inspector is going to cite existing conditions as code violations, they need to be diligent and not inadvertently approve other major non conformities on the property.

June 15, 2016

Bulletin 3

Page 2 of 2





Bulletin 4 – Systems installed on roofs of: multi-story homes, tile of concrete shingles, and or of pitches greater than 4:12.

Building inspectors accessing roofs with tile, or concrete shingles, and or of pitches greater than 4:12, are highly discouraged. When damaging the finished surfaces of a roof is not of a concern, I.E. for roofs with asphalt shingles or rolled asphalt roofing, providing access to any roof is the contractors responsibility.

If an inspector proposes to access a roof via ladder, the inspector should make sure it is California Department of Industrial Relations - General Industry Safety Orders compliant (commonly referred to as "OSHA compliant"). Moreover, the inspector needs to be aware when fall protection is required due to the height and or steepness of the pitch of the roof.

Although it's the contractor's obligation to provide the safe access, it's the inspector's responsibility to understand what safe access is - it's the AHJ's responsibility to have safety training.

Avoid all potential issues – all the more reason for the inspector to stay on the ground and use photos (See bulletins 2 and 7.)

Inspection access to the roofs of the structures depicted below is highly discouraged.



See: California Department of Industrial Relations - General Industry Safety Orders:

https://www.dir.ca.gov/title8/3276.html

June 15, 2016

Bulletin 4





Bulletin 5 - An unobstructed clear path on roof for firefighters.

The most common disaster that strikes a single family dwelling is fire. However, more fire fighters are injured due to the "in process action" of trying to extinguish a home on fire that "happens" to have a PV system on its roof, than are injured due to the PV system igniting a home on fire. The paramount goal of a building inspector should be to confirm code compliance with fire code related requirements, most important of all the fire code related requirements – a clear path around PV panels for fire fighter access.

PV panels can significantly impede roof ventilation efforts of firefighters despite a code compliant clear path, lessoning this path width only compounds those issues. A clear path for firefighters will also help maintain a safe emergency recuse path to bedroom windows.

In general a 3 feet clear path is required between panels and the edges/ridges of the roof surface.



June 15, 2016

Bulletin 5





Bulletin 6 - Correction notice writing basics.

Clearly describe "observations."

Clearly describe corrective actions necessary.

Cite accurate applicable Code Section.

Example 1 - "Methods of Construction"

"All conduit shall be fastened"

Does not equal

"EMT conduit on roof adjacent photovoltaic array on south facing roof is not fastened within 3 feet of each termination point and horizontal runs are not supported and fastened every 10 feet." Please see CEC Article 358.50 for further information.

Example 2 - "Inaccurate Construction Plans"

"PV system installation does not match construction plans"

Does not equal

"The expedited permit was issued based upon standard plan information that is not accurate in comparison to the proposed as built installation. Please reconcile via plan check the wiring methods, make, model and rating of the inverter, as well as the number of modules and their location on the roof of the structure. (Plans depict a 5000W SolarEdge SEP4000A-US inverter with integrated disconnect and 2 strings of 9 modules not a 7000W Sunpower inverter with 3 strings of 12 modules.)"

Example 3 - "Unlawful Existing Structure"

"Room addition does not have permit"

Does not equal

"A cursory review of permit records reveals the "flat roof" room addition approximately 20 feet x 10 feet in size and located at the North-East part of the dwelling, appears to have been constructed without the benefit of building permits and inspection approvals. Approval for the installation of the small PV system will require reconciliation of the permit records or retroactive permits for the work not benefit of permits."

June 15, 2016

Bulletin 6



RECOMMENDED PRACTICES

Series 1 - AB 2188 Requirements

Issue 1 – Single Inspection Guidelines for Small Residential Rooftop Solar Energy Systems

1. Issue Statement:

What should be considered sufficient to the Authority Having Jurisdiction (AHJ) in order to comply with the single inspection requirements of AB 2188?

2. Background:

All California jurisdictions are mandated by the State to adopt an expedited PV permitting process in accordance with Assembly Bill 2188. The Solar Energy Action Committee (SEAC) has identified practical methods of compliance with the AB 2188 requirements in an effort to assist local building officials.

3. Current Status:

SEAC has identified successful single inspection procedures currently in use by several jurisdictions. In addition, SEAC is providing innovative recommendations that can be used to develop AB 2188 compliant single inspection procedures.

4. Key considerations:

The objective of these recommendations is to facilitate system approval in one inspection. Many of the solutions simply require a greater education, relationship, and communication of expectations between the AHJ and the installer.

5. Recommendation(s):

- The installer should ensure that a qualified individual who is familiar with the applicable codes and installation procedures be onsite at time of inspection to provide access to the system and all components and to answer any questions from the inspector.
- Access to the roof should be provided in accordance with the latest CAL/OSHA guidelines.
- Approved construction documents and installation instructions shall be available onsite at time of inspection for major system components, including: Inverters, Modules, Power Optimizers, and Racking and Mounting systems.

For the most recent version of the document, please refer to the SEAC website at <u>www.SEACgroup.org</u> SEACRP1/201511-v1

Bulletin 7 - Page 1 of 3

- Affidavits, signed by the installer and homeowner, may be considered by the AHJ as verification of installation of the smoke and carbon monoxide alarms required by the California Residential Code.
- Ongoing training by qualified organizations regarding the one inspection process and installation procedures should be encouraged on a regional basis.
- 6) The AHJ may adopt specific details on photographic documentation that is required at time of inspection as an aid of the inspection process and as a tool to be used in lieu of removal of specific components.

SEAC recommendations include the following photo guidelines that may be used for inspection of items not readily accessible to the inspector and should include, but not necessarily be limited to:

Photographs shall be of sufficient clarity to clearly demonstrate the elements being inspected, and shall include evidence that the photograph is connected to the property of the inspection site.

Include photo(s) of:

- PV module label. If more than one module type is used on a project, there must be a photo for each different module, including the micro-inverter.
- Method of flashings at attachments and penetrations, including the sub flashing beneath tiles.
- 3) Method of grounding and bonding PV modules and racking systems.
- 4) Wire management under PV modules.
- 5) Conduit penetrations of the roof and inaccessible portions of the structure.
- Proof of height of conduit above the roofing material to verify temperature de-rate calculations.
- Attic-run conduit and fastening methods.
- 8) All junction and/or combiner boxes with the cover removed.
- 9) Any required labels or markings not readily accessible at time of inspection.

6. Applicable to whom:

The recommendations would apply to all solar energy stakeholders.

Disclaimer: The Recommended Practices of SEAC are tools and information to benefit the solar energy industry. Recommended Practices published by SEAC are non-binding and/or regulatory.

For the most recent version of the document, please refer to the SEAC website at <u>www.SEACgroup.org</u> SEACRP1/201511-v1

Bulletin 7 - Page 2 of 3

Recommended Practices Number: SEACRP1/201511-v1 Revision: 1 Revision Date: November 15, 2015 Date of Conceptual Consensus: October 29, 2015 Date of Majority Committee Consensus: November 15, 2015

For the most recent version of the document, please refer to the SEAC website at <u>www.SEACgroup.org</u> SEACRP1/201511-v1

Bulletin 7 - Page 3 of 3



RECOMMENDED PRACTICES

Series 1 - AB 2188 Requirements

Issue 2 – Methods to reduce follow-up inspections for Small Residential Rooftop Solar Energy Systems

1. Issue Statement:

What methods should be considered in order to reduce follow-up inspections for roof mounted PV systems without compromising safety or quality?

2. Background:

Failed inspections are creating more work for AHJs and installers adversely affecting the wide adoption of PV installations.

Many inspections fail due to insufficient:

- · Understanding of codes and standards
- Preparation for the inspection
- Quality of work
- Training
- Communication of expectations between inspector and installer

3. Key considerations:

 Economic factors such as financial incentive deadlines, state/local rebates, proposed tax credits, and utility rate changes could create an increase in the demand for solar and the number of PV installations. In light of this, installers and inspectors are encouraged to work together to find new solutions.

 Some of the solutions simply require the effective use of resources through a consistent and efficient streamlined process. One way to practice efficiency and avoid a follow-up inspection would be for both the inspector and installer to be prepared, and to allow for minor corrections to be made during the inspection process.

For the most recent version of the document, please refer to the SEAC website at <u>www.SEACgroup.org</u> SEACRP2/201511-v1

Bulletin 8 Page 1 of 3

4. Recommendation(s):

The Solar Energy Action Committee (SEAC) has identified the following practical methods to assist Installers and AHJs:

- A. Persons involved in the installation and inspection of PV systems must be qualified and trained in the areas of electrical theory, the applicable parts of NEC/CEC Chapters 1 through 4 and NEC/CEC Articles 690 and 705. Qualification and training should also include applicable PV related fire and building codes. Training should be done on a regular basis.
- B. Installers and inspectors should be familiar with the inspection related material of the California Solar Permitting Guidebook and the manufacturer's installation instructions.
- C. The installer can expedite the inspection process by having a qualified representative on site to assist with the inspection. With the agreement of the installer and inspector minor corrections may be performed at time of inspection to avoid a re-inspection.
- D. The California Solar Permitting Guidebook inspection checklist is encouraged to be used so that both the inspector and installer will know what to expect. However, if an AHJ develops a different inspection checklist, this checklist should be provided when an installation permit is issued. AHJs should be encouraged to post their inspection criteria and policies on their website.
- E. The installer can expedite the inspection process by providing an applicable completed quality control and code based installation checklist to the inspector.
- F. Both inspectors and installers should be encouraged to regularly attend local IAEI and ICC chapter meetings for training regarding the latest code requirements and installation practices. These forums provide an opportunity for continual dialog between the inspectors and installers to help foster better communication and stay updated on new technology from the manufacturers.
- G. The installer can expedite the inspection process by providing the following equipment and documents for the inspection:
 - 1) OSHA approved ladder capable of providing access to roof.
 - AHJ-approved plans and permit(s).
 - 3) Installation instructions at least for the following electrical equipment:
 - a. PV modules
 - b. PV inverter
 - c. Mounting/racking system

For the most recent version of the document, please refer to the SEAC website at <u>www.SEACgroup.org</u> SEACRP2/201511-v1

Bulletin 8 Page 2 of 3

d. Grounding and bonding

- 4) Tools for removal / reattachment of PV modules and equipment.
- 5) Extra labels (notably "WARNING: PHOTOVOLTAIC POWER SOURCE").
- 6) Any required AHJ affidavit.
- 7) Documentation as described in SEAC Recommended Practices #1.

5. Applicable to whom:

The recommendations would apply to all solar energy stakeholders.

Disclaimer: The Recommended Practices of SEAC are tools and information to benefit the solar energy industry. Recommended Practices published by SEAC are non-binding and/or regulatory.

Recommended Practices Number: SEACRP2/201511-v2 Revision: 1 Revision Date: November 23, 2015 Date of Conceptual Consensus: November 19, 2015 Date of Majority Committee Consensus: November 23, 2015

For the most recent version of the document, please refer to the SEAC website at <u>www.SEACgroup.org</u> SEACRP2/201511-v1

Bulletin 8 Page 3 of 3



RECOMMENDED PRACTICES

Series 1 - AB 2188 Requirements

Issue 3 - Expedited PV Permitting Process Guidelines for Small Residential Rooftop Solar Energy Systems

<u>Objective:</u> To facilitate submission of uniform, correct, and complete expedited PV permitting applications and reviews in a timely manner.

1. Issue Statement:

Permit requirements and processing can be plagued with misunderstandings. Permit applications which are submitted incorrectly and/or incomplete, require resubmission creating delays in approval.

2. Background:

Permitting processes vary widely across jurisdictions creating confusion for permit applicants; in addition, permitting processes which are not clearly defined or are overly complex create confusion and misunderstandings resulting in additional costs for both the applicants and reviewers in the processing of permit applications. Some permit applications require resubmission due to insufficient preparation or understanding of codes and standards.

3. Current Status:

As of September 30, 2015 all California jurisdictions were mandated by the State to adopt an expedited PV permitting and inspection process in accordance with Assembly Bill 2188.

4. Key considerations:

The State of California continues to set far-reaching climate and energy goals. SEAC has conducted research and identified the following important mandates, acts and facts to take into consideration:

- AB 2188 requires all California jurisdictions to adopt an ordinance to create a streamlined permitting process for residential PV systems in substantial conformance with the California Solar Permitting Guidebook.
- The California Solar Rights Act is intended to encourage timely and cost-effective installation of solar energy systems, promote the use of solar energy systems, and to limit obstacles to their use.

Bulletin 9 Page 1 of 3

 Economic factors such as financial incentive deadlines, state/local rebates, proposed tax credits, and utility rate changes could create an increase in the demand for solar and the quantity of PV permit applications.

5. Recommendation(s):

Many of the solutions simply require a greater education, relationship, and communication of expectations between the AHJ and the Installer.

The following are practices to consider assisting permit applicants and jurisdictions:

- Use of the California Solar Permitting Guidebook (CSPG) checklists and standard plan

 refer to additional resources (3). Checklist and permitting documentation details
 should be clear and made available on the jurisdictions website.
- Consider the use of PV permit application software which automates the toolkits provided in the CSPG. Refer to SEAC website for currently available PV permit software.
- In accordance with AB2188, jurisdictions shall clearly inform applicants of all the documentation required and the method of submission.
- 4) Training for applicants and jurisdictions in the use of the CSPG Submittal Requirements Bulletin (Toolkit Document #1) and the Eligibility Checklist (Toolkit Document #2) is provided by the CSE – details can be found at: <u>https://energycenter.org/</u>
- Use of the SEAC website as an information resource for the solar industry SEAC publishes all Recommended Practices on its website to further assist the solar industry on common issues, these Recommended Practices can be found at: <u>www.seacgroup.org</u>
- Increased communication between all industry stakeholders to decrease PV permit application inconsistencies through active participation in local organization meetings such as SEAC, CALBO, IAEI, ICC, CalSEIA and CSE.

6. Benefits:

The above recommendations will aid in achieving a successful implementation and adoption of AB 2188 permitting process. The recommendations will significantly simplify the process, reduce human error, reduce inconsistencies as well as standardize the permit application process, and decrease application review time. The successful adoption of expedited permitting will help the State of California reach its clean energy and environmental goals and in turn, improve our communities.

7. Applicable to whom:

The recommendations would apply to all solar energy stakeholders.

Bulletin 9 Page 2 of 3

Disclaimer: The Recommended Practices of SEAC are tools and information to benefit the solar energy industry. Recommended Practices published by SEAC are non-binding and/or regulatory.

Additional Resources:

- (1) Assembly Bill 2188 Muratsuchi
 - http://leginfo.legislature.ca.gov/faces/billNavClient.xhtml?bill_id=201320140AB2188
- (2) California Government Code, ARTICLE 2. Adoption of Regulations [65850 65863.13] <u>http://leginfo.legislature.ca.gov/faces/codes_displaySection.xhtml?lawCode=GOV§ion.whtml?lawCode=GOV§ion.xhtml?lawCode=GOV§i</u>
- (3) California Solar Permitting Guidebook Spring 2015 https://www.opr.ca.gov/docs/California Solar Permitting Guidebook Spring 2015.pdf
- (4) California Solar Rights Act <u>https://lib.sandiego.edu/law/documents/centers/epic/Solar%20Rights%20Act-<u>A%20Review%20of%20Statutes%20and%20Relevant%20Cases.pdf</u>
 (5) Senate Bill 1222 Leno
 </u>
- http://leginfo.legislature.ca.gov/faces/billNavClient.xhtml?bill_id=201120120SB1222

Recommended Practices Number: SEACRP3/201601-v1 Revision: 1 Revision Date: January 28, 2015 Date of Committee Consensus: January 28, 2016

Bulletin 9 Page 3 of 3


RECOMMENDED PRACTICES

Series 1 - AB 2188 Requirements

Issue 4 – Educational Resources for Small Residential Rooftop Solar Energy Systems

<u>Objective:</u> To provide educational resources to assist in achieving a safe and codecompliant PV installation in a timely and cost- effective manner.

1. Issue Statement:

The lack of appropriate information, education and training can hamper the successful transition and deployment of solar energy systems. An inadequately trained workforce can create unnecessary obstacles and delays resulting in an increased cost to industry.

2. Background:

Information, education and training on solar energy systems are abundant and can prove overwhelming. PV training can vary greatly in regard to consistency, regulations, code content and quality. A poorly skilled workforce can potentially compromise industry standards, quality and safety.

3. Current Status:

The adoption of AB 2188 drives the need to provide reliable and updated information and training.

4. Key considerations:

Quality educational resources are critical to the development and maintenance of a skilled and knowledgeable workforce.

The State of California continues to set far-reaching climate and energy goals. There is a constant evolution of PV system related technologies, product standards, code and utility requirements, permitting and inspection procedures for jurisdictions. This presents a challenge for all stakeholders.

5. Recommendation(s):

Many of the solutions simply require better education, relationship, and communication of expectations between all stakeholders.

Bulletin 10 Page 1 of 3

The following are practices and resources to consider

- The California Solar Permitting Guidebook (CSPG) is a current resource based on the California codes that provides regulatory, design, installation guidance for designers, installers and inspectors of residential PV systems - refer to additional resources (1).
- Increased communication between all industry stakeholders is essential and should be encouraged through active participation in local organization meetings such as SEAC, IAEI, CALBO, CaISEIA, SEIA, CSE and ICC.
- Use of the SEAC website as an information resource for the solar industry SEAC publishes all Recommended Practices on its website to further assist the solar industry on common issues, these Recommended Practices can be found at: www.seacgroup.org

For future assistance SEAC plans to develop the following:

- 4) An online interactive resource that provides consistent information trending in the solar industry and lists available solar training with website links should be developed
- 5) A research group to identify information and training gaps in the industry
- 6) A minimum criteria guideline for all available training programs
- An online forum for all industry stakeholders to come together to share, collaborate and communicate

6. Benefits:

The above recommendations will aid in promoting consistent information, education and training on AB 2188 statewide standards, as well as other valuable solar training programs. This will result in creating a skilled and knowledgeable workforce. Studies show an improvement in productivity and the quality of work following training, thus resulting in a more efficient and effective workforce. Training is also one way of ensuring employees feel valued; it increases staff loyalty and decreases staff turnover.

In addition, a successfully skilled workforce is a strong workforce that will help achieve safe and compliant installation of solar energy systems.

7. Applicable to whom:

The recommendations would apply to all solar energy stakeholders.

Disclaimer: The Recommended Practices of SEAC are tools and information to benefit the solar energy industry. Recommended Practices published by SEAC are non-binding and/or regulatory.

Bulletin 10 Page 2 of 3

Additional Resources:

(1) California Solar Permitting Guidebook Spring 2015 https://www.opr.ca.gov/docs/California Solar Permitting Guidebook Spring 2015.pdf

Recommended Practices Number: SEACRP4/201601-v1 Revision: 1 Revision Date: January 28, 2015 Date of Committee Consensus: January 28, 2016

Bulletin 10 Page 3 of 3

(Slide 13) "Westlaw Next" California Code of Regulations: <u>https://govt.westlaw.com/calregs</u>

"Find Cal Law" California Law: <u>http://leginfo.legislature.ca.gov</u>

(Slide 16) The County Building and Safety Division was originally established as a department in March 1933 by the Los Angeles County Board of Supervisors. This action was taken in the wake of the Long Beach earthquake, which brought to focus the importance of maintaining and enforcing effective building laws.

(Slide 22) California Solar Permitting Guidebook

As of January 21, 2016, the most recent version of the California Solar Permitting Guidebook can be found online at:

https://www.opr.ca.gov/docs/California_Solar_Permitting_Guidebook_Spring_2015.pdf



(Slide 22)

Critical Path or Critical Path Method (CPM)

Term used in California Construction law that denotes milestone markers/scheduling of the construction process. CPM is not a "Bar Chart" or "Gant Chart." CPM prevails in court. Just one of many recognized books on the subject has been produced by Kenneth C. Gibbs, Esq:

http://www.jamsadr.com/gibbs/

Mr. Gibbs body of work on the subject can be found online at:

http://www.wklawbusiness.com/store/products/california-construction-lawseventeenth-prod-0735592578/hardcover-item-1-0735592578



(Slide 29 and 30) Access to work - OSHA

"When in doubt - stop - ask questions"

CAL/OSHA - The most convenient and user friendly information regarding CAL/OSHA requirements as they pertain to the construction industry and ladder use may be found at the following web site:

https://www.dir.ca.gov/dosh/etools/08-001/care.htm

Cal/OSHA [eTcols [Portable Ladder Safety] inspection, Use and Maintenance	
CALOSHA Portable Ladder Safety ctool	
General Information Regulations Design and Construction Ladder Selection Inspection, Us Employee Training Resources Credits	se, and Maintenance
Contact	t Cal/OSHA Disclaimer
inspection, Use and Maintenance	
Inspection of Ladder	
Ladders need to be inspected by a qualified person for visible defects before each use. While in through conditions that may impact its integrity. A ladder with compromised integrity will not be s	use, a ladder may go safe for use.
General Inspection	
Employees should conduct inspections for general ladder safety for all portable ladder types by	checking the followings:
Ladders should not have any damage, lack of structural integrity, missing components or low	ose parts
Warning Damaged or worn ladders should be destroyed.	
The steps or rungs must be tight and secure to the side rails.	
 All hardware and fittings need to be properly and securely attached. 	
Movable parts must be tested to see that they operate without binding or without too much f	free play.
 All labels should be intact and readable. 	
 Ladders shall be free of oil, grease, or slippery materials. 	
 A ladder that has been exposed to fire or strong chemicals should be discarded. 	
 All accessories such as leg levelers, paint shelves, stand-off shelves, etc. are in good condition. The lodder base shell be pleased as a secure and level facting. When peaseses, lodder level 	tion.
 The ladder base shall be placed on a secure and level rooting, when necessary, ladder level achieve equal rail support on uneven surfaces. 	elers shall be used to
The ladder base must have the slip resistant material.	
 While inspecting extensions ladders you need to make sure that: 	
 Ropes and pulleys are in good condition. 	

Portable Ladder Safety - Inspection, Use and Maintenance Page 2 of 10
 Ladder extension locks move freely and lock correctly Rung locks are on the rails of the top section to ensure the top section will not fall. Extension guide brackets are secure and in place
Additional inspection
In addition to the general inspection elements mentioned above, there are ladder type specific elements that also need to be inspected. Do not use the ladder if you find any of the ladder-specific conditions listed below present in the type of ladder you are inspecting.
 For metal ladders, also check for the followings:
 loose rungs, nails, boits screws and other metal parts dented rungs or rails sharp edges, corners and burrs damage from corrosion bonde and brasica
 bends and breaks taos or stickers reading "CAUTION-Do Not Use Around Electrical Equipment" or similar wording.
 For wooden ladders also inspect the followings: integrity of rungs and rails chips, splits, cracks and splinters in the rails holes and knots loose / wingly parts.
 painted wooden parts (transparent paint is OK)
 Fiberglass or plastic ladders should be inspected for the following elements as well: cracks, chips and splinters deformed rails or rungs from heat, chemical or environmental exposure bends and breaks
 For self supporting step ladders, also inspect for the following: the two front legs should be of the same length and the two hind legs should also be of the same length spreaders are intact and lock correctly
Use of Ladder
Position Ladders Correctly
 Keep the area around the top and bottom of a ladder clear.
 When using a ladder in a crowded area, erect warning signs or barricades to guide traffic away from the foot of the ladder. If this is not possible, have someone hold and guard the bottom of the ladder.
 Rest the base of ladder on a spot away from hallways, passageways, doorways, driveways or heavy traffic areas. Never set up a ladder in front of a door unless the door is locked or a guard is posted.
https://www.dir.ca.gov/dosh/etools/08-001/care.htm 6/16/2016















Portable Ladder Safety - Inspection, Use and Maintenance	Page 9 of 10
Never store materials on a ladder.	
 Store wood ladders where they will not be exposed to excessive heat or dampness. Store fibe they will not be exposed to sunlight or other ultraviolet light sources. 	rglass ladders where
 Be sure that ladders are properly supported and secured when in transit. Vibration and bumpir objects can damage them. 	ng against other
 Store ladders on racks, which give them proper support when not in use. 	
 Metal bearings of extension ladder rung locks and pulleys should be lubricated periodically, an maintenance periods whenever necessary. 	d between regular
· Ropes on extension ladders should be in good condition, If they become frayed or badly worn,	replace them.
 DO NOT use ladders with broken or missing steps, rungs, cleats, safety feet, side rails, or other 	er defects.
Keep the ladders free of oil, grease, or slippery materials all the time by cleaning frequently.	
Store all ladders to protect them from weathering effects.	
Prohibited Uses	
Listed below are the most common prohibited uses	
Use of damaged or defective ladders	
Use of ladders inappropriate for the specific job	
Hand carry loads or equipment while on a ladder	
Reach to the point where you lose your balance	
Stand or work on the top cap or the step below the top cap of a stepladder	
Stand or work on the top 3 rungs of an extension ladder	
Place ladders on boxes, barrels, pick- up trucks or scaffolds or equipment	
Use portable ladders in a horizontal position as a plank, platform, or scaffold etc.	
Splice together short ladders to make longer ladders	
Use ladders with only a single rail	
Use ladders in high winds	
Use extension ladders without maintaining minimum overlap	
Using ladder that does not meet the required duty rating	
Replace all frayed or badly worn ropes	
https://www.dir.ca.gov/dosh/etools/08-001/care.htm	6/16/2016
Portable Ladder Safety - Inspection, Use and Maintenance	Page 10 of 10
Copyright © 1995 - 2016 State of California	

Fall Protection



Youth in Construction eTool	Page 1 of 3
CA.	
Cal/OSHA [eTools] Youth in Construction] Fall Protection	
Youth in Construction deal	
Click here For Students and Young Employees FOR TEACHERS AND EMPLOYERS	
MAIN MENU	
Fall Protection	
As trainers of your students and young workers, you are responsible for educating them on workplace health and safety including (but not limited to): safe work practices, worker's rights, the importance of learning in safety meetings and other trainings, and complying with rules and regulations. To reduce the risk of injury and increase productivity, see the information below:	
What is Required by Cal/OSHA	
 Stopping Fails Fact Sneet When training your students and young workers make sure and review with them their information on 	
Fail Protection.	
What Is Required by Cal/OSHA	
Cal/OSHA has a number of regulations related to Fall Protection in construction - found in Title 8 of the California Code of Regulations (T8CCR). The specific Cal/OSHA safety requirements that apply to your trainees depends on the types of construction activities they will actually be performing. The complete set of Title 8 regulations can be found at: www.dir.ca.gov/samples/search/query.htm	
Working Heights and Trades - In the Cal/OSHA regulations there are many working heights that trigger the use of Fall Protection depending on the trade, the job being performed, the height at which the work is done and the dangers below the working surface. The Cal/OSHA regulations related to Fall Protection in construction can be found in Chapter 4. Division of Industrial Safety, Subchapter 4. Construction Safety Orders	
The following is an overview of the regulations in Title 8 for Fall Protection in construction (not all of the applicable Title 8 regulations are given below)	
 Article 16. Standard Railings (T8CCR 1620 - 1621) Article 19. Floor, Roof and Wall Openings (T8CCR 1632 - 1633) Article 21. Scaffolds - General Requirements (T8CCR 1635.1 - 1637) Article 22. Scaffolds - Various Types (T8CCR 1640 - 1655) Article 24. Fall Protection (T8CCR 1669 - 1672) Article 2. Standard Specifications (T8CCR 3209 - 3239) in Subchapter 7. General Industry Safety Orders 	
http://www.dir.ca.gov/dosh/etools/08-010/TE_FallProtection.htm	6/16/2016



Youth in Construction eTool	Page 3 of 3
sloped roof surfaces steeper than 7:12 or other sloped surfaces steeper than 40 degrees not otherwise adequately protected under the provisions of these orders.	
• Safety Nets (T8CCR 1671) - requires safety nets where the elevation is 25 feet or more above the ground, water surface, or continuous floor level below, and when the use of personal fall arrest systems, personal fall restraint systems, positioning device systems or more conventional types of protection are clearly impractical, the exterior and/or interior perimeter of the structure shall be provided with an approved safety net extending at least 8 feet horizontally from such perimeter and being positioned at a distance not to exceed 10 feet vertically below where such hazards exist, or equivalent protection provided safety nets shall extend outward from the outermost projection of the work surface as follows:	*
Vertical distance from working level Minimum required horizontal distance of outer edge of to horizontal plane of net. net from the edge of working surface.	
Up to 5 feet 8 feet	
More than 5 feet up to 10 feet 10 feet	
More than 10 feet but not to exceed 30 13 feet feet.	
Fall Protection Plan	
person. The plan permits work to be carried on in a designated area, without conventional fall protection, and requires alternate measures to be used to reduce any fall hazard. There must be constant observation by a safety monitor. The area of the work is known as an "controlled access zone" and only trained workers can enter.	
Copyright © 1995 - 2016 State of California	
http://www.dir.ca.gov/dosh/etools/08-010/TE_FallProtection.htm	6/16/2016

For a more detailed view of CAL/OSHA requirements as they pertain to the construction industry, visit the following part of the CAL/OSHA website and download the "CAL/OSHA Pocket Guide For The Construction Industry."



https://www.dir.ca.gov/dosh/PubOrder.asp

For a comprehensive view of CAL/OSHA requirements as they pertain to the construction industry, see the California Code of Regulations Title 8 Division 1.

https://govt.westlaw.com/calregs/Index?transitionType=Default&contextData=(sc.Default)

Note - There are Construction Safety Orders (Subchapter 4) and General Industrial Safety Orders (Subchapter 7). The "outline" of the regulations are as follows:

California Code of Regulations - Title 8 Industrial Relations

Division 1. Department of Industrial Relations

Chapter 4. Department of Industrial Safety:

Subchapter 4. Construction Safety Orders

Subchapter 7. General Industry Safety Orders

(Slide 47) a. Typical Contractors Quality Control Checklist: Curtesy SolarCity www.solarcity.com/SolarCity

Rooftop to Inverter

- Ensure all equipment matches approved plans (modules, mounting hardware, J-box/combiner box, etc.)
- Mounting hardware is not altering roof in a manner that will cause the elements to enter building (Tiles are not lifted from tile hooks, Comp flashing installed properly under comp etc.)
- No loose connections with nuts, bolts, screws, clamps and interlocks at arrays
- Interlocks are installed in all necessary locations within the array
- Max spans between penetrations do not exceed approved plans
- No low hanging wires under array with properly spaced wire clips
- When ABS vents are re-routed under array, ensure the vent is always running up the roof, never horizontal or downhill.
- Fire setbacks are within NFPA requirements and CA Fire Code (req 96) and as shown on approved plans
- Array layout matches approved plans
- Structure of attic matches approved plans and when applicable rafter upgrade matches plans
- Conduit is installed per code (elevated from roof surface with supports no more than 10 feet apart, within 3 feet of all connections, fittings are rated for exterior use in a wet location, grounded and run in a good workmanship like manner, etc.)
- Conduit is run so that the opening is facing down the roof under array

- Wires in conduit do not exceed conduit fill for conduit
- Bond bushings are in place at every conduit termination with set screws tightened
- The conductors are sized according to the appropriate ampacity with correct Temp. derate and conduit fill calculations
- Inverter matches approved plans
- Inverter is installed with proper work clearance Per NEC 110.26
- All labeling is per code on conduit and equipment

Inverter to Utility

- Wires in conduit match approved plans and are appropriate for AC side amperage
- Conduit is installed per code (supports no more than 10 feet apart, within 3 feet of all connections, fittings are rated for exterior use in a wet location, grounded and run in a good workmanship like manner, etc.)
- Conduit is sized appropriately for number and size of wires in it
- Irreversible crimp is placed on the GEC for the house/main panel or two ground rods are placed for system grounding.
- Proper size and brand back feed breaker is installed
- Back feed breaker is placed at opposite end of bussing from main breaker
- Ensure the 120 percent rule is followed with End fed panels and 100 percent rule is followed with center fed panels
- Make sure Main Panel GEC connection is accessible(ufer or ground rods)
- All system labeling is in place and per code
- Site plan plaque is installed on main panel and accurately portrays equipment location

(Slide 47) a. Typical Contractor Quality Control/Commissioning Documentation Courtesy Verengo Solar <u>http://www.verengosolar.com/</u>

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501		
Verengo Quality Commissioning		Date: 08/04/2015
PROJECT INFORMATION		
A1. Project # (SO-xx-xx-xxx) A2. Project Last Name: A3. Foreman Name: A4. Electrician Name: Equipment List: Select all equipment shown on the ap NEC	so1505172	nspected per the 2014
 1.0 Array 2.0 Micro Inverters 3.0 Roof Conduit 4.0 Junction / Combiner Box 5.0 Roof Conduit Penetration 6.0 Wall Conduit 7.0 DC Disconnect 8.0 String Inverter 9.0 Load Center 10.0 Production Meter 11.0 AC Disconnect 12.0 Wall Conduit Penetration 13.0 Subpanel 14.0 Interconnection 15.0 Production & Monitoring A5. Homeowner: Greet homeowner and confirm equipment location on plan set. 		
Submitted by to 8/03/2015 14:03 PDT, captured at 0	8/03/2015 13:47 PDT	

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 A6. Address: Clearly show a full view of the customers home from the street with Verengo sign present. (Address and module required in photo for Sunrun projects) Submitted by at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Mobile Apps For How You Do Business - powered by Canvas (<u>www.gocanvas.com</u>) Page: 2

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 A8. Safety Harness Anchor: Clearly show the location of the safety harness anchor in relation to the working area if applicable (Required for roof teams). 1.0 ARRAY Array # 1 Submitted by the second Page: 4

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 1.1 Mounting System Penetration: Clearly show a screen fit picture of a properly installed mounting penetration with hardware and flashing. 1.2 Mounting System Splice: Splice or expansion joint \checkmark properly installed with 1/2" gap. 1.3 Mounting System Span: All mounting system V penetrations within the maximum span of the mounting system specifications. 1.4 Mounting System Cantilever: All rail cantilever is \checkmark less than 33% of the max span for each penetration. (See Field Notes) 1.5 Mounting System EGC: EGC is properly bonded to V the mounting system. 1.6 Mounting System Layout: Mountng system layout V installed per plan. 1.7(a) Array Layout: Array installed per plan without M changes. ۰. Submitted by at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Page: 5 Submission ID: d2147ec67887f257-143864840993 Mobile Apps For How You Do Business - powered by Canvas (<u>www.gocanvas.com</u>)

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 1.7(b) Shading Measurements: Collected shading V measurements. 1.8 Array Clearance: Clearly show the array height off the roof surface. CD 00 -9 5 4 3 0 Submitted by a second by a to 8/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Mobile Apps For How You Do Business - powered by Canvas (<u>www.gocanvas.com</u>) Page: 6



Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 1.11 Array Azimuth: Clearly show the array azimuth within +/- 5 degrees of the approved plan set. 165°S 240 n FREE MUSIC FOR EVERYTHING YOU DO Google play 1.12 Module Mid Clamp: Mid Clamps are properly 1 installed. 1 1.13 Module End Clamp: End clamps are properly mounted with rail exposure min of 2", max 3" past the module frame. \checkmark 1.14 Module Spacing: All modules are evenly spaced with a min 1/4 inch, max 1" between them. \checkmark 1.15 Module Cantilever: All modules are installed with a mimimum of 4" cantilever and maximum of 17" portrait / 10" landscape. 1.16 Array Leveling: The array is level accross the V roof surface and height between modules less than 1/4". Submitted by at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Page: 8 Mobile Apps For How You Do Business - powered by Canvas (www.gocanvas.com)

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 1.17(a) Array Wire Management: Clearly show underneath the array from the ridge down that all conductors are secure, protected from UV and not visibly hanging. 1.17(b) Array Wire Management: Clearly show underneath the array and between the rails that all conductors are secure, protected from UV and not visibly hanging. 1.18 Module EGC: ECG is properly bonded to the V module. 1.19 Module Damage: Modules are free of surface \checkmark scratches and scrapes. 1.20 Roof Damage: Roof is free of any Verengo \checkmark caused damage. 3.0 ROOF CONDUIT Roof Conduit # 1 Submitted by at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Mobile Apps For How You Do Business - powered by Canvas (<u>www.gocanvas.com</u>) Page: 9



Verengo Quality Commissioning	Date: 08/04/2015
3.2 Roof Conduit Support: Clearly show a srcreen fit picture of a properly installed roof conduit support.	
3.3 Roof Conduit Paint: Roof conduit is evenly painted to match the roof surface without significant overspray. 3.4 Roof Conduit Workmanship: Roof conduit runs	
well planned and installed in a neat and workmanlike manner.	(V)
NEC 110.3(B) - Installation Listing NEC 110.12 - Workmanship NEC 310.10(D) - Direct Sunlight NEC 314.15 - Damp or Wet Locations NEC 344.14 - Dissimilar Metals NEC Article 358 - EMT NEC 690.43 - Equipment Grounding	AKAAAA
NEC 590.64 - Grounding Physical Damage	¥.
Combiner Box #	1
	•

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 4.1 Junction / Combiner Box Installation: Clearly show a screen fit picture of the combiner box with the cover open and distance of 1" or less between array. NEC 110.3(B) - Installation Listing >>> NEC 110.12 - Workmanship NEC Article 200 - Identification of Grounded Conductors NEC 310.10(D) - Direct Sunlight AV-YV NEC 690.16 - Fuses NEC 690.31 - Methods Permitted NEC 690.34 - Box Access 5.0 ROOF CONDUIT PENETRATION Roof Conduit Penetration # 1 Submitted by the second Page: 12

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 5.1 Roof Conduit Penetration Flashing: Clearly show a screen fit picture of the electrical roof penetration flashing or conduit decending from the roof. 5.2 Roof Conduit Penetration Bottom: Clearly show a screen fit picture of the sealed electrical roof penetration from below. NEC 110.3(B) - Installation Listing V NEC 110.12 - Workmanship 6.0 WALL CONDUIT Wall Conduit # 1 Submitted by the second at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Mobile Apps For How You Do Business - powered by Canvas (<u>www.gocanvas.com</u>) Page: 13

Torrance, CA 90	501
Verengo Quality Commissioning	Date: 08/04/2015
6.1 Wall Conduit Support: Clearly show a wall mounted conduit run that is properly supported.	
6.2 Wall Conduit Paint: Wall conduit is evenly painted to match the customers home. 6.3 Wall Conduit Workmanship: Wall conduit runs well planned and installed in a neat and workmanlike manner. NEC Article 358 - EMT NEC 110.12 - Workmanship	N N N
7:0 DC DISCONNECT	
DC Disconnect #	1
Submitted by at 08/03/2015 14:03 PDT, captured at 08/03/2 Submission ID: d2147ec67887f257-1438634840993	2015 13:47 PDT Page: 14

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 7.1 DC Disconnect Installation: Clearly show a screen fit picture of the DC disconnect with the cover open. NEC 110.3(B) - Installation Listing NEC 250.96 - Bonding Enclosures NEC 690.31 - Methods Permitted NEC 690.47 - Grounding Electrode System **8.0 STRING INVERTER** String Inverter # 1 Submitted by at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Mobile Apps For How You Do Business - powered by Canvas (<u>www.gocanvas.com</u>) Page: 15

Verengo Solar 20285 South Western Av Suite # 200 Torrance, CA 90501	e
Verengo Quality Commissioning	Date: 08/04/2015
picture of the inverter label.	
	13.007
(Slide 47) a. Contractor Quality Control/Commissioning Documentation (continued)



Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 10.1 Production Meter: Clearly show a screen fit picture of the properly installed production meter with the cover open. 10.2 Production Meter Tag: Tag installed on production 10.2 Production Meter Tay: Tay Installed on meter. NEC 110.3(B) - Installation Listing NEC 110.27 (A)(2) - Guarding of Live Parts NEC 300.3(B) - Conductors of Same Circuit NEC 690.31 - Methods Permitted NEC 250.96 - Bonding Enclosures NEC 690.47 - Grounding Electrode System **11.0 AC DISCONNECT** AC Disconnect # 1 Submitted by at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Page: 18 Mobile Apps For How You Do Business - powered by Canvas (www.gocanvas.com)

(Slide 47) a.	Contractor	Quality	Control/0	Commissioning	Documentation	(continued)
---------------	------------	---------	-----------	---------------	---------------	-------------

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 11.1 AC Disconnect: Clearly show a screen fit picture of the properly installed AC disconnect with the cover open. @... NY 16 11.2 AC Disconnect Tag: Tag installed on AC NEC 110.27 (A) (2) - Installation Listing NEC 110.12 - Workmanship NEC 110.27 (A)(2) - Guarding of Live Parts NEC 240.21(B)(1) - Location in Circuit, AKA - 10 ft. tap rule. (Tapped systems only) < </>
</ NEC 250.96 - Bonding Enclosures NEC 690.8(A) - Circuit Sizing NEC 690.9(A)(B)(C) - Overcurrent Protection (Next Fuse Size > Max inverter(s) continuous output x 1.25) (OCPD less than 50 amps in 5 amp increments) (OCPD greater than 50 amps in 10 amp increments) NEC 690.13(A) - Disconnect Location NEC 690.31 - Methods Permitted NEC 690.47 - Grounding Electrode System \checkmark 14.0 INTERCONNECTION Submitted by a to 8/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Mobile Apps For How You Do Business - powered by Canvas (<u>www.gocanvas.com</u>) Page: 19



Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 14.2 Interconnection Main Breaker: Clearly show a screen fit picture of the main service breaker with breaker sizes legible. 14.3 Interconnection Solar Breaker/Tap: Clearly show a screen fit picture of the solar breaker or tap with equipment sizes legible. NEC 110.3(B) - Installation Listing NEC 110.12 - Workmanship NEC 250.52 - Grounding Electrode NEC 250.96 - Bonding Enclosures NEC 250.120 - EGC Installation NEC 250.122 - EGC Size NEC 250.166 - Grounding Electrode Size ***** Submitted by _______at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submission ID: d2147ec67887f257-1438634840993 Page: 21 Mobile Apps For How You Do Business - powered by Canvas (www.gocanvas.com)



20285 South Wes Suite # 20 Torrance, CA	tern Ave 0 90501
Verengo Quality Commissioning	Date: 08/04/2015
15.5 Production Equipment Power: Clearly show the total power (WATTS) being generated on the equipment display.	
	R TECHNOLOGY
16.0 INSTALLATION COMPLETE	
Submitted by a second at 08/03/2015 14:03 PDT, captured at 08/ Submission ID: d2147ec67887f257-1438634840993 Mobile Apps For How You Do Business - powered by Canvas (www.gocany	03/2015 13:47 PDT Page: 23

Verengo Solar 20285 South Western Ave Suite # 200 Torrance, CA 90501 Verengo Quality Commissioning Date: 08/04/2015 16.1(a) Wall Equipment 1: Clearly show full view of all completed wall mounted equiment with covers closed. 16.1(b) Wall Equipment 2: Secondary photo if all wall mounted equipment was not able to be captured in first photo. 16.2 Production Meter Communication: Clearly show the production meter communication code or symbol, serial #'s and meter tag. 210+ce 833 396 61 CL 200 240V 3W FM2S 727X299056 60HZ TA 30 Kh 18.0 Kt 1.0 www.SolarServiceHelp.com 61833396 at 08/03/2015 14:03 PDT, captured at 08/03/2015 13:47 PDT Submitted by Page: 24 Submitted by Conversion and Conversi

Verengo Quality Commissioning	Date: 08/04/2015
16.4 Equipment ON (String Inverter): - MSP Solar Breaker - Subpanel Solar Breaker(s) - Load Center Breakers(s)	
- AC Disconnect(s) - DC Disconnect(s) (Non Inverter Integrated) 16.5 Equipment OFF (String Inverter):	\checkmark
- Inverter(s) - DC disconnect(s) (Inverter Integrated) 16.6 Clean Up: Home has been cleaned of all installation	X
debris from roof, yard and other working areas. 16.7 Foreman Inspection: I have inspected this project to the best of my ability to meet the quality standards of Verengo Solar and this project is SUBSTANTIALLY COMPLETE.	
REDLINES: 16.8 Layout Redlines: Clearly show a screen fit photo of the plan set identifying all layout changes WITH new shade measurement locations marked.	
16.9 Electrical Redlines: Clearly show a screen fit photo of the single line diagram identifying all electrical changes made.	
FINISH WORK: Finish Work Item 1: Finish Work Photo 1: Finish Work Item 2: Finish Work Photo 2: Finish Work Item 3: Finish Work Photo 3: 16.10 Foreman Comments: Describe finish work	Panel Upgrade
required and customer comments if any. panel upgrade still required and tie in of solar. Submission Location:	
	columbre Rd Parker Rd Barker Rd
	Sierra Rd
	Council and San

(Slide 47) c. Single Line Diagram

CEC 215.5 Diagram of Feeders. If required by the authority having jurisdiction, a diagram showing feeder details shall be provided prior to the installation of the feeders. Such a diagram shall show the area in square feet of the building or other structure supplied by the feeder, the total calculated load before applying the demand factors, the demand factors used, the calculated load after applying demand factors, and the size and the type of conductors to be used.

Example - Single Line Diagram (From California Solar Permitting Guidebook)







(Slide 48 - 52) Photos and information via: Fire Fighter Safety and Emergency Response for Solar Power Systems *Final Report* - A DHS/Assistance to Firefighter Grants (AFG) Funded Study Prepared by: Casey C. Grant, P.E. Fire Protection Research Foundation. See:

http://www.nfpa.org/research/fire-protection-research-foundation/projects-reports-andproceedings/for-emergency-responders/fireground-operations/fire-fighter-safety-andresponse-for-solar-power-systems



(Slide 53) Photo: Gatis Sluka - Cartoon About Electricity Posted On-Line January 30, 2014

(Slide 54-56) Photo credits and information courtesy Georgia Tech Research Institute via Grant SH-1942-09-06-f13 from OSHA, USDOL. For a detailed PowerPoint, see:

http://www.oshainfo.gatech.edu/nfpa/NFPA70E-1.pdf



(Slide 71) - https://energycenter.org/





(Slide 87) California Solar Permitting Guidebook Tool Kit 7

(Slide 87) California Solar Permitting Guidebook Tool Kit 7 "19 Point Checklist"

SECTION 1: Field Inspection Guide for Rooftop Photovoltaic (PV) Systems Standard Plan

Make sure all PV system AC/DC disconnects and circuit breakers are in the open position and verify the following.

- 1. All work done in a neat and workmanlike manner (CEC 110.12).
- 2. PV module model number, quantity and location according to the approved plan.
- 3. Array mounting system and structural connections according to the approved plan.
- 4. Roof penetrations flashed/sealed according to the approved plan.
- 5. Array exposed conductors are properly secured, supported and routed to prevent physical damage.
- 6. Conduit installation according to CRC R331.3 and CEC 690.4(F).
- Firefighter access according to approved plan.
- 8. Roof-mounted PV systems have the required fire classification (CBC 1505.9 or CRC R902.4).
- Grounding/bonding of rack and modules according to the manufacturer's installation instructions that are approved and listed.
- 10. Equipment installed, listed and labeled according to the approved plan (e.g., PV modules, DC/DC converters, combiners, inverters, disconnects, load centers and electrical service equipment).
- 11. For grid-connected systems, inverter is marked "utility interactive."
- 12. For ungrounded inverters, installation complies with CEC 690.35 requirements.
- 13. Conductors, cables and conduit types, sizes and markings according to the approved plan.
- 14. Overcurrent devices are the type and size according to the approved plan.
- 15. Disconnects according to the approved plan and properly located as required by the CEC.
- 16. Inverter output circuit breaker is located at opposite end of bus from utility supply at load center and/or service panelboard (not required if the sum of the inverter and utility supply circuit breakers is less than or equal to the panelboard bus rating).
- 17. PV system markings, labels and signs according to the approved plan.
- 18. Connection of the PV system to the grounding electrode system according to the approved plan.
- Access and working space for operation and maintenance of PV equipment such as inverters, disconnecting means and panelboards (not required for PV modules) (CEC 110.26).

SECTION 2: Comprehensive Inspection Reference

GENERAL

- 1. Module manufacturer, make, model and number of modules match the approved plans. (CBC 107.4)
- DC PV modules are listed to UL 1703. Ac modules are listed to UL 1703 and UL 1741. (CEC 110.3, 690.4 & CBC 1509.7.4 & CRC R908.1.5)
- Modules are attached to the mounting structure according to the manufacturer's instructions and the approved plans. (CEC 110.3[B], CBC 107.4 & CRC R908.1.4)
- 4. Roof penetrations/attachments are properly flashed. (CBC Chapter 15 & 2012 CRC Chapter 9)
- 5. Rooftop systems are designed in accordance with the CBC. (CBC 1509.7 & CRC R908.1)
- Roof access points, paths and clearances need to comply with the CFC. (CFC 605.11.3.1 605.11.3.3.3, CRC R331.4.1 through R331.4.2.4)
- 7. PV installation shall comply with requirements of the standard plan.
- PV system operating at 80 volts or greater shall be protected by a listed DC arc fault protection. (CEC 690.11)
- 9. All work done in a neat and workmanlike manner. (CEC 110.12)

ELECTRICAL REQUIREMENTS

PV Array Configuration

- 10. DC modules are properly marked and labeled. (CEC 110.3, 690.4[D] & 690.51)
- 11. AC modules are properly marked and labeled. (CEC 110.3, 690.4[D] & 690.52)
- PV modules are in good condition (i.e., no broken glass or cells, no discoloration, frames not damaged, etc.). (CEC 110.12[B])
- 13. Residential one- and two-family dwelling limited to maximum PV system voltage of 600 volts. (CEC 690.7)

Bonding and grounding

- 14. A complete grounding electrode system is installed. (CEC 690.47[A] & [B])
- Modules are bonded and grounded in accordance with the manufacturer's installation instructions, that are listed and approved, using the supplied hardware or listed equipment specified in the instructions and identified for the environment. (CEC 690.43 & 110.3[B])
- Racking systems are bonded and grounded in accordance with the manufacturer's installation instructions, that are listed and approved, using the supplied hardware or listed equipment specified in the instructions and identified for the environment. (CEC 690.43 & 110.3[B])
- Properly sized equipment grounding conductor is routed with the circuit conductors. (CEC 690.45, 250.134[B] & 300.3[B])
- AC and DC grounding electrode conductors are properly connected as required by code. Separate electrodes, if used, are bonded together. (CEC 690.47, 250.50 & 250.58)

Part 3: PV Toolkit for Local Governments

- Bonding fittings are used on concentric/eccentric knockouts with metal conduits for circuits over 250 volts. (CEC 250.97) (see also exceptions 1 through 4)
- Bonding fittings are used for ferrous metal conduits enclosing grounding electrode conductors. (CEC 250.64[E])

PV Source/output Circuit Conductor Management

- Cables are secured by staples, cable ties, straps, hangers or similar fittings at intervals that do not exceed 4.5 feet. (CEC 334.30 & 338.12[A][3])
- Cables are secured within 12 inches of each box, cabinet, conduit body or other termination. (CEC 334.30 & 338.12[A][3])
- 23. Cable closely follows the surface of the building finish or of the running boards. (CEC 690.4[F] & CFC 605.11.2 & CRC R331.3) NOTE: see Section 12 below for additional requirements on routing of conductors for fire fighter safety concerns.
- 24. Exposed single conductors, where subject to physical damage, are protected. (CEC 230.50[B] & 300.5[D])
- Exposed single conductors used for ungrounded systems are listed and identified as "PV wire." (CEC 690.35[D][3]) For other conductor requirements for ungrounded systems, see CEC 690.35(D).

Conductors

- 26. Exposed single conductor wiring is a 90° C, wet rated and sunlight resistant type USE-2 or approved/listed PV wire. (CEC 690.31[B] & 110.2) If the wiring is in a conduit, it is 90° C, wet rated type RHW-2, THWN-2, or XHHW-2. (CEC 310.15)
- 27. Conductor insulation is rated at 90°C to allow for operation at 70°C+ near modules. (CEC 310.15)
- 28. Grounded conductor is identified white or gray. (CEC 200.6)
- 29. Open conductors are supported, secured and protected. (CEC 338.12[A][3] & 334.30)
- 30. Conductors are not in contact with the roof surface. (CEC 334.30)
- DC conductors inside a building are in a metal raceway or MC metal-clad cable that complies with 250.118(10), or metal enclosures. (CEC 690.31[E])
- 32. DC wiring methods shall not be installed within 25 cm (10") of the roof decking or sheathing except where directly below the roof surface covered by the PV modules and associated equipment. (CEC 690.31[E][1])
- If more than one nominal voltage system conductor is installed in the raceway, permanent identification and labeling is required. (CEC 200.6[D] & 210.5[C])
- For underground conductor installations, the burial depth is appropriate and warning tape is in place. (CEC 300.5[D][3] & Table 300.5)
- 35. Aluminum is not placed in direct contact with concrete. (CEC 250.120[B] & 110.11)
- 36. PV circuit and premises wiring is separated. (CEC 690.4[B])
- PV system conductors shall be grouped and identified. (CEC 690.4[B])

Overcurrent Protection

- Overcurrent protection devices (OCPD) in the DC circuits are listed for DC operation. (CEC 110.3[A], [B] & 690.9[D])
- 39. Overcurrent protection devices shall be provided per the approved plans. (CEC 690.9[A])
- 40. Combiner box is listed to UL 1741.
- PV output OCPD is located at the opposite end of the bus from the feeder connection, unless otherwise approved. (CEC 705.12[D][7])

Electrical Connections

- Crimp terminals are listed and installed using a listed tool specified for use in crimping those specific crimps. (CEC 110.3[B] & 110.14)
- Pressure terminals are listed for the environment and tightened to manufacturer recommended torque specifications. (CEC 110.11, 110.3[B] & 110.14)
- Connectors are listed for the voltage of the system and have appropriate temperature and ampere ratings. (CEC 110.3[B] & 110.14)
- Twist-on wire connectors are listed for the environment (i.e., wet, damp, direct burial, etc.) and installed per manufacturer's instructions. (CEC 110.11, 110.3[B], 110.14 & 300.5[B])
- 46. Power distribution blocks are listed. (CEC 690.4 & 2011 NEC 314.28[E])
- Terminals containing more than one conductor are listed for multiple conductors. (CEC 110.14[A] & 110.3[B])
- Connectors and terminals used other than class B and C stranded conductors (fine stranded conductors) are listed and identified for use with specific conductor class or classes.. (CEC 110.14[A] & 110.3[B])
- Connectors that are readily accessible and operating at over 30 volts require a tool for opening. (CEC 690.33[C])
- 50. All connectors are fully engages, tight and secure. (CEC 110.3[B] & 110.12)
- Wiring and connections of inverters, PV source circuits, etc., and all interconnections are performed by qualified personnel. (CEC 690.4[E])

Disconnects

- 52. Disconnects used in DC circuits are listed for DC operation and located as allowed by the AHJ. (CEC 110.3)
- Disconnects are installed for all current carrying conductors of the PV source. (CEC 690.13 690.14 & 690.35)
- Disconnects are installed for the PV equipment. NOTE: For inverters and other equipment that are energized from more than one source, the disconnecting means must be grouped and identified per AHJ's requirements. (CEC 690.15)
- Disconnects and overcurrent protection are installed for all ungrounded conductors in ungrounded PV power systems. (CEC 240.15 & 690.35)
- Where connectors are used as disconnecting means, they shall be used in accordance with CEC 690.33.E (CEC 690.33.E & 690.17)

Part 3: PV Toolkit for Local Governments

Inverters

- 57. Inverters are listed to UL 1741. (CEC 690.4[D]) NOTE: grid-tied system inverters need to be identified for use in interactive power systems.
- 58. Point of connection is at a dedicated breaker or disconnect. (CEC 705.12[D][1])
- Where a back-fed breaker is used as a utility interconnection means, the breaker is not marked "line and load." (CEC 110.3[B], 705.12[D][5])
- 60. Listed AC and DC disconnects and overcurrent protection are grouped and identified. (CEC 690.15)
- No multiwire branch circuits are installed where single 120-volt inverters are connected to 120/240-volt load centers. (CEC 690.10[C])
- 62. The barrier is reinstalled between the AC, DC wiring and communication wires. (CEC 110.3[B] & 110.27)

Signs and Labels

- All interior and exterior DC conduit, enclosures, raceways, cable assemblies, junction boxes, combiner boxes and disconnects are marked. (CFC 605.11.1, CEC 690.31[E][3], CEC 690.31[E][4], 690.17 & 690.53 & CRC R331.2)
- 64. The markings on the conduits, raceways and cable assemblies are every 10 feet, within one foot of all turns or bends and within one foot above and below all penetrations of roof/ceiling assemblies, walls and barriers. (CFC 605.11.1.4, CRC R331.2.4, CEC 690.31[E][3] & CEC 690.31[E][4])
- Marking is placed adjacent to the main service disconnect in a location clearly visible from where the disconnect is operated. (CFC 605.11.1.3 & CRC R331.2.3)
- 66. The markings say "WARNING: PHOTOVOLTAIC POWER SOURCE" and have 3/8-inch (9.5 mm) minimum-sized white letters on a red background. The signs are made of reflective weather resistant material. (CFC 605.11.1.1, 605.11.1.2 & CRC R331.2.1 R331.2.2 & CEC 690.31[E)][3] & 690.31[E][4])
- 67. Where PV circuits are embedded in built-up, laminate or membrane roofing materials in roof areas not covered by PV modules and associated equipment, the location of circuits shall be clearly marked. (CEC 690.4[F])
- Required labels shall be permanent and suitable for the environment. The following labels are required as applicable.

Table 1. Signage Requirements for PV systems					
Code Section	Location of Label	Text			
CEC 690.5(C)	Utility-interactive inverter & battery enclosure	WARNING: ELECTRIC SHOCK HAZARD IF A GROUND FAULT IS INDICATED, NORMALLY GROUNDED CONDUCTORS MAY BE UNGROUNDED AND ENERGIZED			
CEC 690.35(F)	All enclosures with ungrounded circuits or devices which are energized and may be exposed during service	WARNING: ELECTRIC SHOCK HAZARD. THE DC CONDUCTORS OF THIS PHOTOVOLTAIC SYSTEM ARE UNGROUNDED AND MAY BE ENERGIZED.			
CEC 690.14(C)(1)	On the main service when DC wiring is run through the building and the DC disconnect is located other than at the main service	DC DISCONNECT IS LOCATED			
CEC 690.14(C)(2)	On the AC and DC disconnects	PHOTOVOLTAIC SYSTEM DISCONNECT			
CEC 690.53	On the DC disconnects	OPERATING CURRENT OPERATING VOLTAGE MAXIMUM SYSTEM VOLTAGE SHORT CIRCUIT CURRENT			
CEC 690.54	At interactive points of interconnection, usually the main service	RATED AC OUTPUT CURRENT AMPS NORMAL OPERATING AC VOLTAGE VOLTS			
CEC 690.56(B)/ 690.14(D)(4), 705.10 2011 CEC 690.4(H)	At the electrical service and at the PV inverter if not at the same location	A directory providing the location of the service disconnecting means and the photovoltaic system disconnecting means			
CEC 690.17	On the DC disconnect and on any equipment that stays energized in the off position from the PV supply	WARNING! ELECTRIC SHOCK HAZARD. DO NOT TOUCH TERMINALS. TERMINALS ON BOTH THE LINE AND LOAD SIDES MAY BE ENERGIZED IN TH OPEN POSITION.			
CEC 705.12 (D)(7)	Inverter output OCPD	WARNING: INVERTER OUTPUT CONNECTION DO NOT RELOCATE THIS OVERCURRENT DEVICE.			
CFC 605.11.1.4, CEC 690.31(E)(3), 690.31(E)(4), CRC R331.2.4	On conduit, raceways and enclosures, mark every 10 feet, at turns, above/ below penetrations	WARNING: PHOTOVOLTAIC POWER SOURCE. Note: This label shall have a red background with white letterina			

Part 3: PV Toolkit for Local Governments

Page | 164

(Slide 87) California Solar Permitting Guidebook Tool Kit 7 Section 2 (*continued*) and (Slide 107-109)

FIRE SAFETY REQUIREMENTS

- Rooftop-mounted PV panels and modules have the proper fire classification rating. (CBC 1509.7.2 & CRC R908.1.2)
- Conduit, wiring systems and raceways for photovoltaic circuits are located as close as possible to the ridge, hip or valley and from the hip or valley as directly as possible to an outside wall to reduce trip hazards and maximize ventilation opportunities. (CFC 605.11.2 & CRC R331.3)
- Conduit runs between sub arrays and to DC combiner boxes are installed in a manner that minimizes total amount of conduit on the roof by taking the shortest path from the array to the DC combiner box. (CFC 605.11.2 & CRC R331.3)
- DC Combiner Boxes are located so that conduit runs are minimized in the pathways between arrays. (CFC 605.11.2 & CRC 331.3)
- DC wiring in enclosed spaces in buildings is installed in metallic conduit or raceways. Conduit runs along the bottom of load bearing members. (CFC 605.11.2 & CEC 690.4[F] & CRC R331.3)
- 6. All roofs have an access point that does not place ground ladders over openings such as windows or doors, are located at strong points of building construction, and in locations where the access point does not conflict with overhead obstructions such as tree limbs, wires or signs. (CFC 605.11.3.1 & CRC R331.3)
- Roofs with slopes greater than 2:12 have solar panel layouts with access pathways that comply with approved roof plan that meet the following criteria: (some exceptions apply, see diagrams in the California Solar Permitting Guidebook)
 - A. Hip Roofs: Panels/modules are located so that there is a 3-foot wide clear access pathway from the eave to the ridge on each roof slope where panels/modules are located. (CFC 605.11.3.2.1 & CRC R331.4.2.1)
 - B. Hips and Valleys: If panels/modules are placed on both sides of a hip or valley they are located no closer than 18 inches to a hip or valley. If the panels are located on only one side of a hip or valley that is of equal length, then the panels can be placed directly adjacent to the hip or valley. (CFC 605.11.3.2.3 & CRC R 331.4.2.3)
 - C. Single Ridges: Panels/modules are located so that there are two 3-foot wide access pathways from the eave to the ridge on each roof slope where there are panels/modules installed. (CFC 605.11.3.2.2 & CRC R331.4.2.2)
 - D. Ridges: Panels/modules are located no higher than 3 feet from the top of the ridge in order to allow for fire department smoke ventilation operations. (CFC605.11.3.2.4 & CRC R331.4.2.4)
 - E. Access pathways are located at a structurally sound location capable of supporting the load of fire fighters accessing the roof. (CFC 605.11.3.2.1 & CRC R331.4.2.1)

STRUCTURAL AND OTHER CODE REQUIREMENTS

List the structural requirements by the Authority Having Jurisdiction.

California Solar Permitting Guidebook